

Zestawienie oznakowania poziomego
PROJEKT PRZEBUDOWY DROGI KRAJOWEJ NR 11
w mieście Oborniki w km 249+350,00 ÷ 250+212,00 na długości 0,862 km.

Rodzaj linii	Lokalizacja		Długość [m]	Współczynnik pow. malowania	Powierzchnia malowania [m ²]
	od km	do km			
1	2	3	4	5	6
LINIE P - 1c					
OŚ	249+391,00	249+421,00	30		
	249+498,50	249+518,50	20		
	249+815,00	249+855,00	40		
	249+974,00	249+994,00	20		
	250+026,00	250+048,00	22		
	250+124,00	250+137,00	13		
PODSUMOWANIE linii P - 1c			145,00	0,12	17,4
LINIE P - 1e					
OŚ	249+448,00	249+476,00	28		
	249+448,00	249+476,00	28		
	249+543,00	249+546,00	3		
	249+761,00	249+764,00	3		
	249+888,50	249+891,50	3		
	249+906,00	249+921,00	15		
	249+916,00	249+931,00	15		
	250+047,50	250+050,50	3		
	250+064,00	250+070,00	6		
	250+066,00	250+069,00	3		
	250+078,00	250+081,00	3		
	250+079,00	250+082,00	3		
	250+092,00	250+104,00	12		
	250+093,00	250+106,00	13		
	250+161,00	250+166,00	5		
	250+209,00	250+212,00	3		
PODSUMOWANIE linii P - 1e			146,00	0,12	17,5
LINIE P - 3b					
	249+456,00		6		
	249+798,00	249+815,00	17		
	249+801,00	249+813,00	12		
	249+836,00	249+846,00	10		
	249+846,00	249+856,00	10		
	249+990,50	250+020,00	29,5		
	249+997,00	250+027,50	30,5		
	250+015,00	250+032,00	17		
PODSUMOWANIE linii P - 3b			132,00	0,18	23,8
LINIE P - 4					
OŚ	249+350,00	249+352,00	2		
	249+410,00	249+448,00	38		
	249+480,00	249+513,00	33		
	249+546,00	249+761,00	215		
	249+856,00	249+888,50	32,5		
	249+891,50	249+901,00	9,5		

CS	249+929,00	249+970,50	41,5		
	250+050,50	250+064,00	13,5		
	250+070,00	250+079,00	9		
	250+082,00	250+088,00	6		
	250+110,00	250+131,00	21		
	250+166,00	250+209,00	43		
PODSUMOWANIE linii P - 4			464,00	0,24	111,4
LINIA P - 7b					
	249+352,00	249+408,00	56		
	249+352,00	249+410,00	58		
	249+513,00	249+543,00	30		
	249+518,50	249+543,00	24,5		
	249+764,00	249+798,00	34		
	249+765,00	249+801,00	36		
	249+813,00	249+836,00	23		
	249+815,00	249+834,00	19		
	249+970,50	249+997,50	27		
	249+970,50	249+995,50	25		
	249+994,00	249+997,00	3		
	250+027,50	250+047,50	20		
	250+069,00	250+078,00	9		
	250+081,00	250+086,00	5		
	250+131,00	250+161,00	30		
	250+137,00	250+158,00	21		
PODSUMOWANIE linii P - 7b			420,50	0,24	100,9
LINIA P - 10					
	249+470,00		8	4,0 m	
	249+482,00		10	4,0 m	
	249+904,50		11	4,0 m	
	249+914,50		7,8	4,0 m	
	249+925,00		10,4	4,0 m	
	250+092,00		10	4,0 m	
	250+101,50		7	4,0 m	
	250+101,50		9	4,0 m	
	250+110,00		10	4,0 m	
PODSUMOWANIE linii P - 10			83,20	0,5	166,4
LINIA P - 11					
	249+833,00	249+888,00	55		
	249+833,00	249+888,00	55		
PODSUMOWANIE linii P - 11			110,00	0,5	55,0
LINIA P - 12					
PRAWA	249+467,00	249+474,00	7		
PODSUMOWANIE linii P - 12			7,00	0,5	3,5
LINIA P - 13					
LEWA	249+447,00	249+457,00	10		
	249+912,00	249+917,00	5		
	249+906,00	249+912,00	6		
	250+095,00	249+912,00	6		
PRAWA	249+926,00	249+935,00	9		
	250+102,00	250+108,00	6		
	250+168,00	250+172,00	4		
PODSUMOWANIE linii P - 13			46,00	0,2625	12,1
LINIA P - 14					
	249+449,00		6,5		
	249+481,00		6,5		
	249+815,00		3,5		

	249+893,00		3,5	
	249+901,00		6,5	
	249+929,00		6,5	
	250+088,00		6,5	
	250+114,00		6,5	
PODSUMOWANIE linii P - 14		46,00	0,375	17,3

P -8b				
	40+35+8+70+50+20+45	268	18	
PODSUMOWANIE P - 8b		268,00	1,59	28,6
P - 8f				
	70+50+100+60+90+40	410	27	
PODSUMOWANIE P - 8f		410,00	2,72	73,4
LINIA P - 21				
0,5*(26,5*15+1,4*9,4+1*2,6+1,5*6,8+1,75*26,2+1,4*9,40+1,3*9,35+1,5*10,20+1,7*7,2			261	
PODSUMOWANIE linii P - 21		261,08	0,38	99,2

ŁĄCZNIE 726,56 m2